

Bid Form

Harnett County Anderson Creek C&D Landfill Expansion

Bidder agrees to perform all the work described in the Specifications and shown on the Contract Drawings for the lump sum and unit prices listed in Bid Schedule A below.

Measurement and Basis for Payment:

Some of the line items in the Bid Schedule may include approximate quantities as estimated by the Engineer. The Contractor shall not rely on the quantities given, but shall instead estimate all quantities independently as required to complete the Proposal. The Bid Schedule outlines each item and the corresponding lump sum or unit price listed by the Contractor. The price associated with each lump sum item shall be the full compensation paid for the work described, regardless of the Engineer's or Contractor's estimated quantity. For Lump Sum items, no claim shall be made by the Contractor for deviations between the Contractor's estimated and the actual quantity required to complete the work described, wherein no measurement will be made.

A description of measurement and payment for each Lump Sum and Unit Price Bid item can be found in Section 01025, Measurement and Payment, of the Specifications.

Unit Price Deviations:

The Bidder is responsible for providing unit prices consistent with typical industry norms for the work described. Unit prices which appear inconsistent with typical prices for similar work shall be justified by the Bidder at the request of the Engineer. Providing unit prices which do not reasonably reflect the work described, either high or low, which are not justified satisfactorily to the Engineer, may deem the Bidder non-responsive and invalidate the Bidder's Proposal.

A. **Bid Schedule A:**

Pay Item Number	Description	Spec. Reference	Estimated Quantity¹	Units	Unit Cost	Extended Cost
1.0	Site Preparation	02110	1	LS	Lump Sum	
2.0	Earthwork	02222/02223	1	LS	Lump Sum	
2.1	Overexcavation & Backfill	02222/02223	4,000	CY		
3.0	Erosion and Sedimentation Control:	-----	-----	-----	-----	-----
3.1	Temp. Gravel Construction Entrance/Exit	02270	1	EA		
3.2	Silt Fence	02270	700	LF		
3.3	Stone Filter Fence	02270	50	LF		
3.4	18" Diam. CPE (Type S) (Includes 2 flared end sections) (C-A)	02720	50	LF		
3.5	Filter Berm	02720	1	EA		
3.6	Drainage Channel DC-12A	02270	350	LF		
3.7	Drainage Channels DC-12B and DC-12C	02270	1,000	LF		
3.8	Drainage Channels DC-A and DC-B	02270	460	LF		
3.9	Rip Rap Aprons	02270	2	EA		
3.10	Erosion Control Blanket	02270	3,000 (See Note 2)	SY		
3.11	Revegetation	02930	8	Acres		
4.0	Surveying	01025	1	LS	Lump Sum	
5.0	Bonds, Mobilization, & Insurance	-----	-----	LS	Lump Sum	

The TOTAL BID PRICE for the pay items listed above (Bid Schedule A) is as follows:

(In Words) _____ Dollars and _____ Cents.

(In Numbers) (\$ _____)

Notes:

1. Engineer's estimated quantities are based on in-place quantities. Areas and lengths are based on horizontally projected areas and lengths. No adjustments have been made for stripping topsoil, slopes, uneven contours, overlaps, seams, anchor trenches, compaction factors, etc.
2. The quantity shown for Erosion Control Blanket (ECB) includes slope areas as directed by the Engineer or Owner.

This page intentionally left blank.